



TR&C Masonry

RECIPIENT:

Sarah Graham
Paris

Quote #2	
Sent on	Jul 03, 2024
Total	\$10,805.23

Product/Service	Description	Qty.	Unit Price	Total
Brick Repair	Brick replacement and tuckpointing on south and east facing walls at sidewalk level, up to approx. 3 feet. Replace broken, or damaged brick with best brick match available. Tuckpointing deeply recessed joints and obvious stress cracks as mason deems necessary in this same area with best match given product availability, ensure work blends in as well as possible with original masonry. Labour, material and disposal fees all included in cost Materials being used: King HLM-350 (Heritage) for mortar St. Mary's Portland-lime based for any foundation repairs. Cream Ipstock and reclaimed for brick match. Powdered mortar dyes to colour as needed to match existing mortar.	1	\$5,400.00	\$5,400.00
Stress cracks (water cracks)	tuckpointing stress cracks on Williams street facing wall. This is for labour, material and disposal only; other costs will be Genie lift and permits.	1	\$650.00	\$650.00
65' Genie lift rental and insurance	Total Rentals rental fee, delivery fee, trained operator, insurance and operating costs for boom lift	1	\$2,250.00	\$2,250.00
County Permits and Signage	Permit cost- \$62.15 Signage and county approved blockage- \$1200	1	\$1,262.15	\$1,262.15

A deposit of \$3,241.57 will be required to begin.

Approval of quote must be sent in writing; email or text is preferred.

This quote is valid for the next 90 days, after which values may be subject to change.

Subtotal	\$9,562.15
HST (13.0%)	\$1,243.08
Total	\$10,805.23